



## SUMMARY TEST REPORT

FOR: Andersen Corporation 100 Fourth Avenue North Bayport, MN 55003

SERIES TESTED:

MODEL TESTED

NAFS-08/-11

<u>Test</u>

 Report Number:
 E9918.03-201-47

 Test End Date:
 07/29/2015

 Report Date:
 10/08/2015

 Test Record Retention End Date:
 10/08/2019

400-Series Awning Window A313 DPUP IG Class LC-PG60 Size Tested 35.9 x 71.8 in.\* DP+60/-60

### **Results Summary**

Ease of Operation Resistance to Air Infiltration Resistance to Water Penetration Resistance to Structural Loading Forced Entry Resistance NA <0.01 cfm/ft<sup>2</sup> (ASTM E283) Pass at DP60 (ASTM E547) Pass at DP +60/-60 (ASTM E330) Pass (ASTM F 588)

## CAN/CSA A440-00, Evaluation to the prescriptive requirements were not performed

13 N (3.0 lbf)	
A3	
B4	
C4	
C4	
NA	
F10	
	A3 B4 C4 C4 NA

	See ATI Report No. E9918.01-201-47, and E9918.02-201-47 for
REFERENCE:	complete test results. *See ATI Report # D5486.01-201-47 dated 08/22/14
	for Gateway description.

A copy of this report will be retained by Intertek-ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

### **INTERTEK-ATI**

# INTERTEK-ATI

Karl A. Lips-Eakins Senior Technician Daniel A. Johnson Director - Regional Operations