

## **SUMMARY TEST REPORT**

FOR: Andersen Corporation Report Number: C7172.03-201-47

100 Fourth Avenue North Test End Date: 03/27/2013

Bayport, MN 55003 Report Date: 04/01/2013

Test Record Retention End Date: 04/01/2017

SERIES TESTED: 400 Series Casement Window with Stormwatch Protection

MODEL TESTED CXW145 DPUP IG

NAFS-08/-11 Class LC-PG70 Size Tested 35.9 x 52.6 in.

DP+70/-70

<u>Test</u> Results Summary

Operating EasePass, 18 N (4 lbf) max.Resistance to Air Infiltration0.01 cfm/ft² (ASTM E283)Resistance to Water PenetrationPass at DP70 (ASTM E547)Resistance to Structural LoadingPass at DP70 (ASTM E330)Forced Entry ResistancePass (ASTM F 588)

CAN/CSA A440-00, Evaluation to the prescriptive requirements were not performed

<u>Test</u>	<u>Rating</u>
Operating Ease	18N (4 lbf) max.
Air Tightness	A3
Water Tightness	B5
Wind Load Resistance	C5
Blow-Out	C5

<u>Test</u>	Results Summary
Impact	(N/A)
Pressure Cycling	(N/A)

REFERENCE:	See ATI Report No. C7172.01-201-47 and C7172.02-201-47
	for complete test results.

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

ARCHITECTURAL TESTING, INC

ARCHITECTURAL TESTING, INC

Karl A. Lips-Eakins Daniel A. Johnson

Senior Technician Director of Regional Operations

849 Western Avenue North St. Paul, MN 55117 Phone: 651-636-3835 Fax: 717-764-4129

www.archtest.com