

## **SUMMARY TEST REPORT**

FOR: Andersen Corporation Report Number: C6538.03-201-44

100 Fourth Avenue North

Test End Date: 03/20/2013

Bayport, Minnesota 55003-1096

Report Date: 03/21/2013

Test Record Retention End Date: 03/20/2017

MODEL TESTED: Vinyl Clad Fixed Window SERIES TESTED: 400 Series P5060 IG IR

NAFS-11 Class LC-PG70 Size Tested 59.9 x 71.9 in. DP +70/-80 NAFS-08 Class LC-PG70 Size Tested 59.9 x 71.9 in. DP +70/-80

<u>Test</u> Results Summary

Resistance to Air Infiltration <0.01 cfm/ft² (ASTM E283)
Resistance to Water Penetration Pass at DP70 (ASTM E547)
Resistance to Structural Loading Pass at DP70 (ASTM E330)
Forced Entry Resistance Pass at Grade 10 (ASTM F588)

CAN/CSA A440-00, Evaluation to the prescriptive requirements were not performed

TestRatingAir TightnessFixedWater TightnessB5Wind Load ResistanceC5Blow-OutC5

ASTM E1886 - 02 & 05 ASTM E1996 - 02 & 05

TestResults SummaryImpactNo rips, tears or penetrationsPressure CyclingDP+70/-80

REFERENCE:	See ATI Report No. C6538.01-201-44, C6538.02-201-44 and C6535.02-201-44
	for complete test results.

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

ARCHITECTURAL TESTING, INC

ARCHITECTURAL TESTING, INC

Eric J. Schoenthaler Daniel A. Johnson

Project Manager Director - Regional Operations

849 Western Avenue North St. Paul, MN 55117 Phone: 651-636-3835

Fax: 651-636-3843 www.archtest.com