



## SUMMARY TEST REPORT

FOR: Andersen Corporation 100 Fourth Avenue North Bayport, Minnesota 55003

<u>Test</u>

 Report Number:
 D0667.03-201-47

 Test End Date:
 11/27/2013

 Report Date:
 07/24/2014

 Test Record Retention End Date:
 11/27/2017

SERIES TESTED:A-Series Frenchwood Gliding Patio DoorMODEL TESTEDFWGD43100S IR DPUPNAFS-08/-11Class LC-PG55 Size Tested 50.4" x 119.5" DP +55/-55

<u>Results Summary</u>

Resistance to Air Infiltration	0.01 cfm/ft <sup>2</sup> (ASTM E283)
Resistance to Water Penetration	Pass at DP55 (ASTM E547 and ASTM E331)
Resistance to Structural Loading	Pass at DP +55/-55 (ASTM E330)
Forced Entry Resistance	Pass (ASTM F588)
CAN/CGSB-82.1-M89, Evaluation to the prescriptive requirements were not performed	
Test	Rating
Air Tightness	A3
Water Tightness	B4
Wind Load Resistance	C3
Blow-Out	C3
Forced Entry Resistance	F1
Test	Results Summary
Impact	No rips, tears or penetrations
Pressure Cycling	Pass at DP +55/-55
REFERENCE:	See ATI Report No. D0667.01-201-44 and D0625.02-201-18, for complete test

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

results.

## **ARCHITECTURAL TESTING, INC**

## ARCHITECTURAL TESTING, INC

Eric J. Schoenthaler Project Manager Daniel A. Johnson Director - Regional Operations