



**SUMMARY TEST REPORT**

FOR: Andersen Corporation  
 100 Fourth Avenue North  
 Bayport, MN 55003

Report Number: C7169.03-201-47  
 Test End Date: 05/07/2013  
 Report Date: 07/10/2013  
 Test Record Retention End Date: 07/10/2017

SERIES TESTED: 400 Series Specialty Product - Springline  
 MODEL TESTED: SP802 IG

**NAFS-08/-11** Class LC-PG70 Size Tested 96.0 x 72.1 in. DP+70/-70  
**NAFS-05** N/A

<u>Test</u>	<u>Results Summary</u>
Operating Ease	N/A
Resistance to Air Infiltration	<0.01 cfm/ft <sup>2</sup> (ASTM E283)
Resistance to Water Penetration	Pass at DP70 (ASTM E547)
Resistance to Structural Loading	Pass at DP70 (ASTM E330)
Forced Entry Resistance	Pass (ASTM F 588)

**CAN/CSA A440-00**, Evaluation to the prescriptive requirements were not performed

<u>Test</u>	<u>Rating</u>
Operating Ease	N/A
Air Tightness	Fixed
Water Tightness	B5
Wind Load Resistance	C5
Blow-Out	C5

<u>Test</u>	<u>Results Summary</u>
Impact	(N/A)
Pressure Cycling	(N/A)

<b>REFERENCE:</b>	See ATI Report No. C7169.01-201-47 and C7169.02-201-47 for complete test results
-------------------	--

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

**ARCHITECTURAL TESTING, INC**

**ARCHITECTURAL TESTING, INC**

Karl A. Lips-Eakins  
 Senior Technician

Daniel A. Johnson  
 Director of Regional Operations

849 Western Avenue North  
 St. Paul, MN 55117  
 Phone: 651-636-3835  
 Fax: 717-764-4129  
 www.archtest.com