



## SUMMARY TEST REPORT

FOR:	Andersen Corporation 100 Fourth Avenue North	Report Number: Test End Date:	E3530.03-201-47 12/08/2014	
	Bayport, MN 55003		01/21/2015	
	bay port, into o o o o	Test Record Retention End Date:		
SERIES TESTED:		with Stormwatch Protection		
MODEL TESTED:		CTN30-2S IG IR		
NAFS-0	08/-11	SP-PG70 Size Tested 75.4 x 40.0 in. DP +7	70/-70 psf	
NAFS-05		N/A	N/A	
Test			<u>Results Summary</u>	
Operating Ease			(N/A)	
Resistance to Air Infiltration		, . , ,	<0.01 cfm/ft <sup>2</sup> (ASTM E283)	
Resistance to Water Penetration			Pass at DP70 (ASTM E547)	
Resistance to Structural Loading		Pass at DP70 (ASTM E330)		
Forced Entry Resistance		Pass (ASTM F 588)		
CAN/C	<b>SA A440-00</b> , Evaluation to the prescriptive	e requirements were not performed		
Test		Rating		
Operating Ease		(N/A)		
Air Tightness		Fixed		
Water Tightness		B5	B5	
Wind Load Resistance		С5	C5	
Blow-Out		C5	C5	
Test		<b>Results Summary</b>		
Impact		Zone 4, Missile D	Zone 4, Missile D	
Pressure Cycling		DP +70/-70 psf		

REFERENCE:	See ATI Report No. E3530.01-201-47, E3530.02-201-47, and E3530.04-201-47
REFERENCE.	for complete test results

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

## ARCHITECTURAL TESTING, INC

## ARCHITECTURAL TESTING, INC

Karl A. Lips-Eakins Senior Technician Daniel A. Johnson Director of Regional Operations